Sagebrush Construction

Cost-plus construction estimate

Proposal number: SB-2026-093
Contractor: Sagebrush Construction
Proposal date: 2026-10-05
Project: Cedar Ridge Retreat
Project type: new_home
Pricing basis: cost_plus
Validity: 21 days from proposal date
Contact: estimates@sagebrush.example

PROJECT SUMMARY

Sagebrush offers a cost-plus construction estimate for the same log home project.
Final cost depends on actual labor and material invoices plus the stated fee.

SCOPE OF WORK

- Installed construction scope with owner-supplied window and appliance allowances.
- Cost-plus estimate; see the pricing note for a contradictory fixed-price statement.

LINE ITEMS

LI-01 | Sitework and excavation | 1 | LS | 30,200.00 | 30,200.00
LI-02 | Foundation system | 1 | LS | 55,000.00 | 55,000.00
LI-03 | Log wall package and erection | 1 | LS | 176,000.00 | 176,000.00
LI-04 | Roofing | 1 | LS | 41,500.00 | 41,500.00
LI-05 | Window installation with owner-supplied allowance | 1 | LS | 12,000.00 | 12,000.00
LI-06 | Plumbing rough-in and fixtures | 1 | LS | 23,000.00 | 23,000.00

Sagebrush Construction

Cost-plus construction estimate

LINE ITEMS CONTINUED

LI-07 | Electrical rough-in and fixtures | 1 | LS | 21,000.00 | 21,000.00
LI-08 | Heating and ventilation | 1 | LS | 26,000.00 | 26,000.00
LI-09 | Insulation and drywall | 1 | LS | 30,500.00 | 30,500.00
LI-10 | Interior finishes | 1 | LS | 42,000.00 | 42,000.00
LI-11 | Freight and unloading | 1 | LS | 6,500.00 | 6,500.00
LI-12 | Waste removal and final clean | 1 | LS | 8,000.00 | 8,000.00
Subtotal: $471,700.00
Sales tax: 7.2% included, $33,962.40
Total: $508,162.40

ALLOWANCES

AL-01 | Owner-supplied window allowance | 12,000.00 | Included within LI-05; not additional.
AL-02 | Lighting fixture allowance | 5,000.00 | Included within LI-10; not additional.

EXCLUSIONS

EX-01 | Permits and engineering | Owner responsibility under a separate contract.
EX-02 | Septic and well site utilities | Owner responsibility under separate contracts.
EX-03 | Crane rental | Not included; billed separately if required.
EX-04 | Decorative landscaping | Not included.

Sagebrush Construction

Cost-plus construction estimate

RESPONSIBILITIES

Supplies: Sagebrush Construction, except owner-supplied windows and appliances
Purchases: Sagebrush Construction for included scope
Pays: Sagebrush Construction
Installs: Sagebrush Construction and trade contractors
Coordinates: Sagebrush Construction
Delivers: Sagebrush Construction
Unloads: Sagebrush Construction
Warrants: Sagebrush Construction, one year workmanship

MATERIAL SPECIFICATIONS

Insulation: R-30 wall insulation and R-60 ceiling insulation
Roofing material: Standing-seam metal roof
Log species: Western red cedar log package
Window specification: Owner-supplied triple-pane windows; builder installs
Foundation: Poured concrete full basement with 10-inch walls

FREIGHT AND DELIVERY

Delivery terms: Delivered to site; unloading by Sagebrush. Crane not included.
Freight: Included in LI-11.

PAYMENT TERMS

Deposit: 20% at signing
Payment schedule: monthly cost-plus draws
Payment schedule total: $508,162.40

CHANGE ORDER TERMS

Change order fee: 12% of changed work plus $350 administration fee.

PRICING NOTE

This cost-plus estimate is also offered as a fixed-price contract subject to final scope.

QUALIFICATIONS

Synthetic test document created by BuildScope Check. Not a real offer.
Estimate excludes concealed conditions and owner-directed changes.